


CRP Activities in Kerr County

Shelby Taber Upper Guadalupe River Authority Natural Resources Manager




CRP Water Quality Monitoring

- Quarterly monitoring at 12 sites
- Monthly monitoring at 7 sites
- ALM at 1 site, twice a year





UGRA Water Quality Monitoring





WQ Monitoring Summary 2024

CRP


- 21 sampling events
- 17 sites
- 1,157 parameters tested


UGRA Water Quality Programs

- 58 sampling events
- 43 sites
- 2,443 parameters tested
- 12 water quality investigations













E.coli MPN





2024 Rainfall and Flow












U.S. Drought Monitor

Texas



April 8, 2025 (Released Thursday, Apr. 10, 2025)

Valid 8 a.m. EDT

	Drought Conditions (Percent Area)					
	None	D0-D4	D1-D4	D2-D4	D3-D4	D4
Current	17.87	82.13	58.37	45.93	28.90	13.76
Last Week 04-01-2025	14.77	85.23	67.65	45.93	28.87	13.76
3 Month s Ago 01-07-2025	36.81	63.19	43.63	21.45	13.26	6.30
Start of Calendar Year 01-07-2025	36.81	63.19	43.63	21.45	13.26	6.30
Start of Water Year 10-01-2024	26.09	73.91	34.39	16.62	8.91	3.36
One Year Ago 04-09-2024	54.63	45.37	25.19	9.85	1.97	0.00

Intensity:




The Drought Monitor focuses on broad-scale conditions. Local conditions may vary. For more information on the Drought Monitor, go to https://droughtmonitor.unl.edu/About.aspx

Author:

David Simeral Western Regional Climate Center



droughtmonitor.unl.edu



April 9, 2024

Bacteria Reduction Plan Implementation Status

- Reduce Bacteria Contributions
 - Wildlife
 - Humans
 - Pet Waste
 - Urban Runoff
- Preserve Riparian Areas
- Promote Green Infrastructure





Watershed Stewardship - 2024

- Rainwater Harvesting
 - Rebate up to \$500
 - Rainwater System Grant
 Program
- Water Professionals
 Scholarship
- Brush Management
- Feral Hog Management
- Water Resources Preservation Grant Program








Water Resources Preservation GRANT PROGRAM

Cost-share rebate for design and construction of nature-based infrastructure practices to reduce, infiltrate, filter, and delay stormwater runoff.



Minimum cost-share rebate of \$20,000

PER GUA



Reducing stormwater runoff improves the health of the Guadalupe River.

Design solutions to keep rainfall on your property, reduce flooding, and prevent pollution

Eligible stormwater management practices include:

Bioretention

- Vegetated Filter Strip
- Permeable Pavement
- 💧 Riparian Buffer
- Rainwater Harvesting



Bioretention area next to permeable parking spaces.

For additional information and program documents, visit www.ugra.org or scan



Rainwater Key Notes

1. GUTTER AND DOWNSPOUT CUTOUT TO BE SUPPLIED AND INSTALLED BY METAL BUILDING SUPPLIER MADE READY TO RECEIVE DOWNSPOUTS BY OTHERS

THE FOLLOWING IS TO BE PRICED AS ALTERNATE #1

- 2. SCHED, 40 PVC DOWNSPOUT FULLY SEALED FROM BOTTOM OF GUTTER TO SANITARY TEE FITTING AT COLLECTION PIPE. (TYP) - SUPPLIED AND INSTALLED BY DOWNSPOUT INSTALLER UNDER GC SCOPE. 3. INVERTED OVERFLOW PROTECTION DEVICE NEXT TO EACH DOWNSPOUT -SUPPLIED AND INSTALLED BY DOWNSPOUT INSTALLER UNDER GC SCOPE. X" SDR COLLECTION PIPE AT 24" DEEP FROM TANK TO 5'-6" OFF OF BUILDING FACE - SUPPLIED AND INSTALLED BY DOWNSPOUT INSTALLER UNDER GC SCOPE. PIPE CONTINUATION TO RW TANK BY OWNER. X" SDR COLLECTION PIPE AT 24" DEEP BELOW FOUNDATION- SUPPLIED AND INSTALLED BY DOWNSPOUT INSTALLER UNDER GC SCOPE. GC TO PROVIDE 1 1/4" UG CONDUIT WITH PULL STRING TO RECEIVE WIRING FOR CONTROLS TO TANK PUMP, POWER PROVIDED AND INSTALLED UNDER OWNER'S RAINWATER COLLECTION CONTRACT. RE ELECTRICAL
- 7. 1" SUPPLEMENTAL DOMESTIC MAKEUP WATER LINE FOR BACKUP WATER SUPPLY TO TANK TO 5'-0" OFF BUILDING FACE PROVIDED AND INSTALLED BY GENERAL CONTRACTOR. PIPE CONTINUATION TO RW TANK BY OWNER. RE PLUMBING
- 8. 1" RAINWATER PIPE SUPPLY LINE (COLOR PURPLE) TO 5'-O" OFF OF BUILDING FACE PROVIDED AND INSTALLED BY GENERAL CONTRACTOR . PIPE CONTINUATION TO RW TANK BY OWNER, RE PLUMBING.

Rainwater General Notes

ALL GC INSTALLED PIPE AND FITTING SIZES ARE TO BE CONFIRMED BY OWNERS RAINWATER CONSULTANT PRIOR TO GC PURCHASE AND INSTALLATION. CONTRACTOR TO COORDINATE INSTALLATION WITH RAINWATER TANK INSTALLER. THE FOLLOWING ASSUMPTIVE NOTES ARE FOR BOTH GC AND RAINWATER DESIGNER/INSTALLER REFERENCE.

- COLLECTION PIPE IS SIZED BASED ON A 4" PER HOUR RAIN EVENT. OVERFLOW PROTECTION DEVICES ARE INSTALLED WITHIN THE GUTTERING TO ACCOMMODATE HEAVIER RAIN EVENTS. (RE KEYNOTE 7).
- 2. SHOP DRAWINGS AND SUBMITTALS ARE REQUIRED INCLUDING SYSTEM LAYOUT, COMPONENTS, WIRING DIAGRAMS AND ACCESSORIES WITH BID. THE STORAGE TANK WILL BE SIZED AT 65,639 GALLONS USING PIONEER XL50/02 AND INSTALLED BY A CERTIFIED PIONEER INSTALLER, USING THE MANUFACTURERS PREFERED INSTALL REQUIRMENTS AS PROVIDED BY
- PIONEER USA PREAPPROVAL OF THE PIONEER RAINWATER COLLECTION TANK SYSTEM 4 SUPPLIER/INSTALLER IS REQUIRED. PRIOR TO THE BID DATE. THE BIDDER IS TO SUBMIT PIONEER CREDENTIALS SENT DIRECTLY FROM PIONEER USA TO THE ARCHITECT AND OWNER.
- UPON SYSTEM COMPLETION, INSTALLER WILL PROVIDE FULL TRAINING TO OWNER ON SYSTEM OPERATION AND MAINTENANCE. THE ENTIRE SYSTEM SHALL BE WARRANTED FOR ONE YEAR BEGINNING AT
- OWNER TRAINING SESSION, FOR REFERENCE PURPOSES, FINAL AS-BUILT DRAWINGS ARE TO BE PROVIDED TO THE OWNER AND ARCHITECT AT THE TRAINING SESSION.
- THE BIDDER SHALL HAVE COMPLETED ALL THE REQUIREMENTS OF THE CLASS 200 LEVEL "ACCREDITED PROFESSIONAL" DESIGNATION AS PROVIDED BY THE AMERICAN RAINWATER COLLECTION SYSTEMS ASSOCIATION (ARSCA) AND APPEAR ON THE ARSCA WEB SITE AS HAVING ACHIEVED THAT DESIGNATION.

PROVIDE LANDSCAPE BOXES AT ALL VALVES BELOW GRADE. ALL ITEMS NOT SPECIFICALLY CALLED FOR ON THE PLANS OR IN THE SPECIFICATIONS, BUT NECESSARY TO REASONABLY CONSTRUCT THE SYSTEM TO FULL WORKING ORDER, SHALL BE CONSIDERED INCIDENTAL TO THE OVERALL PROJECT AND WILL BE PROVIDED AT CONTRACTOR EXPENSE. 10. PRIOR TO SUBMITTING BID, RAINWATER SYSTEM INSTALLER IS TO FIELD INSPECT ALL EXISTING CONDITIONS AND ALERT THE OWNER AS TO ITEMS THAT COULD AFFECT THE COST AND INSTALLATION OF THE PROPOSED SYSTEM, SUBMITTING BID CONSTITUTES THAT THE WORK CAN BE PERFORMED WITHOUT ANY CHANGE ORDERS. 11. WHERE TRENCHING IS REQUIRED, THE CONTRACTOR SHALL EXCAVATE




Kerr County Animal Services Facility

198 Spur 100 North Kenville, TX 79929

PRO.ECT NO DATE 20-2302 X/X/XX

> Rainwater Collection Plan



SEAMLESS GUTTER WITH

GUTTER SPECIFICATION

GUTTER SCREENING SEE ARCHITECTURAL PLANS

BY BUILDING CONTRACTOR

THIS LEVEL OF THE DOWNSPOUT MUST BE ABOVE THE TOP OF THE RAINWATER COLLECTION TANK

TO RAINWATER TANK

NOTE: DOWNSPOUTS THAT ARE NOT CONNECTED TO THE RAINWATER COLLECTION SYSTEM SHALL HAVE A METAL DOWNSPOUT. SEE ARCHITECTURAL PLANS FOR METAL DOWNSPOUT SPECIFICATION.

4" PVC DOWNSPOUT PVC SHALL BE SHROUDED WITH METAL

INSTALL 4" PVC

SEE DOWNSPOUT TO COLLECTOR PIPE DETAIL

CLEAN-OUT (TYP.)

WALL

BY RAINWATER SYSTEM INSTALLER

Public Outreach Activities - 2024



- Community Presentations
- Information booths
- Newspaper, radio, social media, and website

- Volunteer Summer Study
- 21st River Clean Up
- EduScape tours
- AgriLife Seminar







Shelby Taber (830) 896-5445 staber@ugra.org